BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work:Repairs to chain link fencing and ssm wall at shooting building road in Mallasandra

Modified Schedule-B

Item No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5. (P.No.	Cum	125.00	400.00	Rupees Four Hundred Only
	Above 125%	Cum	142.51	398.14	Rupees Three Hundred Ninety Eight And Paise Fourteen Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with opc cement @220kgs with 20 mm and down size graded granite metal course aggregate @0.84cum and fine aggregates @0.56 cum machine mixed,laid in layers not exceeding 15cms thick well compacted in foundation,plinth and cills including cost of all materials,labour,HOM OF machinary, curing complete as	Cum	18.75	5400.00	Rupees Five Thousand Four Hundred Only
	Above 125%	Cum	16.65	5348.86	Rupees Five Thousand Three Hundred Forty Eight And Paise Eighty Six Only
3	Filling Available excavated earth(excluding rock) inside cum of foundation upto plinth in layers not exceeding 20cm in depth compacting each deposited layer by ramming after watering with lead upto 50mtr and lift upto 1.5mtr including cost of all labour etc complete as per specification. specificatrion No. KBS 2.9(Item No.2.10 Page	Cum	62.50	130.00	Rupees One Hundred Thirty Only
	Above 125%	Cum	71.26	134.62	Rupees One Hundred Thirty Four And Paise Sixty Two Only
4	KSRB 5.4-4 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13	Cum	70.00	6000.00	Rupees Six Thousand Only
	Above 125%		50.62	5908.55	Rupees Five Thousand Nine Hundred Eight And Paise Fifty Five Only
5	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13(BCSR 2016-2017, Page 23, Item	Cum	42.48	5400.00	Rupees Five Thousand Four Hundred Only

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner

Item No.	Description	Unit	Quantity	Rate, Rs	
				In Figures	In Words
6	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.5 of PWD SR	Sqm	16.67	5900.00	Rupees Five Thousand Nine Hundred Only
7	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1 :2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 ems. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (BCSR	mtr	255.00	850.00	Rupees Eight Hundred Fifty Only
	Above 125%	mtr	81.00	868.16	Rupees Eight Hundred Sixty Eight And Paise Sixteen Only
8	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262,	Cum	708.03	320.00	Rupees Three Hundred Twenty Only
9	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262, Item No 37.3)	Sqm	424.82	700.00	Rupees Seven Hundred Only
10	KSRB 15-18.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications	Sqm	849.64	30.00	Rupees Thirty Only
11	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Page No. 120 Item No. 15.74 of SR 2015-16).	Mtr	849.64	85.00	Rupees Eighty Five Only

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palik
Dasarahalli Zone, Bangalore-73

Scanned by CamScanner